



**NOTES:**

1. WHERE BOTTOM OF EXCAVATION IS IN ROCK WHICH CANNOT BE EXCAVATED TO PROVIDE UNIFORM BEARING FOR THE PIPE, OVEREXCAVATE 6" MINIMUM BELOW DESIGN GRADE, AND REFILL IN 3" THICK COMPACTED LAYERS WITH SELECTED EXCAVATED MATERIAL OR PROVIDE IMPORTED BACKFILL MATERIAL PER SPECIFICATIONS.

# JURUPA COMMUNITY SERVICES DISTRICT

SCALE: NONE		<b>TYPICAL TRENCH DETAIL</b>	DRAWING NO.
DATE: SEPTEMBER 2020			<b>A-1</b>
REV.	APPROVED BY: <i>Sinnaro Yos</i>	ALBERT A. WEBB ASSOCIATES CONSULTING ENGINEERS	W.O. 19-0248
	Sinnaro Yos, P.E. C68607	RIVERSIDE CALIFORNIA	