



NOTE:

1. WHENEVER TRENCH BOTTOM IS INSUFFICIENTLY STABLE, IN THE OPINION OF THE DISTRICT, TO PROVIDE A SUITABLE FOUNDATION FOR THE PIPE, OVEREXCAVATE BELOW DESIGN GRADE AS ORDERED, AND REFILL WITH CAREFULLY PLACED AND SUFFICIENTLY COMPACTED CRUSHED ROCK; OR AS PER SPECIFICATION.

JURUPA COMMUNITY SERVICES DISTRICT

SCALE: NONE

DATE: SEPTEMBER 2020

APPROVED BY:

Sinnaro Yos
Sinnaro Yos, P.E. C68607

WATERLINE SPECIAL BEDDING DETAIL

ALBERT A. WEBB ASSOCIATES
CONSULTING ENGINEERS

RIVERSIDE

CALIFORNIA

DRAWING NO.

A-2

W.O. 19-0248

REV.