



NOTES:

1. PIPE ENCASEMENT TO BE INSTALLED WHERE INDICATED ON THE PLANS AND OR AS DIRECTED IN THE FIELD BY THE DISTRICT.
2. CONTRACTOR SHALL TAKE DUE PRECAUTION AGAINST PIPE FLOATATION DURING THE PLACING OF CONCRETE.
3. IF ANY PIPE APPURTENANCE, SUCH AS OUTLETS, MANWAYS, ETC., ARE REQUIRED IN THE AREA WHERE PIPE ENCASEMENT IS REQUIRED, THE ENCASEMENT SHALL BE FORMED SO THAT REASONABLE ACCESS IS AVAILABLE TO THE PIPE APPURTENANCES.

JURUPA COMMUNITY SERVICES DISTRICT

SCALE: NONE	WATERLINE ENCASEMENT DETAIL	DRAWING NO.
DATE: SEPTEMBER 2020	ALBERT A. WEBB ASSOCIATES CONSULTING ENGINEERS	A-6
APPROVED BY: Sinnaro Yos, P.E. C68607	RIVERSIDE CALIFORNIA	W.O. 19-0248